

Takotna - Road Repair

FY2012 Request: \$25,000
Reference No: 54599

AP/AL: Allocation**Project Type:** Construction**Category:** Transportation**Location:** Takotna**House District:** Interior Villages (HD 6)**Impact House District:** Interior Villages (HD 6)**Contact:** Pat Kemp**Estimated Project Dates:** 04/15/2012 - 06/30/2016**Contact Phone:** (907)465-3900**Appropriation:** Emergency Repairs**Brief Summary and Statement of Need:**

The funding requested is for costs associated with repair work that was performed on the Sterling-Takotna-Ophir Highway, mile post (MP) 35.5 to MP 36.5. The roadway embankment was in poor condition and did not allow for necessary supplies to be delivered to local communities, necessitating the repair of the embankment immediately. This funding would reimburse the department for costs incurred during the emergency repairs done on the Sterling-Takotna-Ophir Highway during this incident.

Funding:	<u>FY2012</u>	<u>FY2013</u>	<u>FY2014</u>	<u>FY2015</u>	<u>FY2016</u>	<u>FY2017</u>	<u>Total</u>
Gen Fund	\$25,000						\$25,000
Total:	\$25,000	\$0	\$0	\$0	\$0	\$0	\$25,000

<input type="checkbox"/> State Match Required	<input checked="" type="checkbox"/> One-Time Project	<input type="checkbox"/> Phased - new	<input type="checkbox"/> Phased - underway	<input type="checkbox"/> On-Going
0% = Minimum State Match % Required	<input type="checkbox"/> Amendment	<input type="checkbox"/> Mental Health Bill		

Operating & Maintenance Costs:

	<u>Amount</u>	<u>Staff</u>
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	
Totals:	0	0

Additional Information / Prior Funding History:

No prior funding history.

Project Description/Justification:

Approximately one mile of the Sterling-Takotna-Ophir Highway, MP 35.5 to MP 36.5, road embankment was saturated with water, creating an impassible, muddy condition for vehicles delivering supplies to local communities and businesses. Delivery of fuel to these communities was urgent. A contract was established to perform basic repairs to the roadway, including placement of a geotextile over the roadway and 18 inches to 24 inches of gravel. Approximately 8,000 cubic yards of gravel was placed on the roadway. State forces also participated in repair of the roadway, however, reimbursement for these costs are not included in this request. Reimbursement for contracted services is requested.